



- Key:
- New Urbis bespoke 'St Annes' lamp post and luminaire to match existing on Wood Street (see inset)
 - Existing trees retained. (Trees to be felled to be undertaken by Fylde Council)
 - Proposed trees: see tree pit detail
 - New bespoke St Annes ferrocast bollards to match existing in Town Centre. Locate as indicated or min. 300mm back from kerb edge and set in concrete foundation.
 - Tapered drop kerb with Marshalls tactile blister paving; colour 'Natural'
 - Tegula block paving; buff colour to match existing on Park Road and Wood Street. Mixed block sizes 60mm deep.
 - Hot rolled asphalt with high percentage of buff aggregate.
 - Sandstone paving slabs 900 x600 x63mm with 100mm wide flush stone trim as detail PCC kerb to roadside to match existing.
 - Existing signage retained
 - New bench to be supplied by Fylde Council.

Work phase boundary

For Hard Landscape Details refer to Drawing Number REG-002/17-SARS003

For Planting Details refer to Drawing Number REG-002/17-SARS004

A	July 17	Amendments after site visit - KTL
Date	Revision	



Technical Services
Development Services
The Town Hall
Lytham St Annes
Lancashire
FY8 1LW

Tel: 01253 658658 E-mail: webmaster@fylde.gov.uk

Drawn By:	KTL	Date:	May 2017
Checked By:	PD	Scale @ A1:	1:250

Project: **ST ANDREW'S ROAD SOUTH AND WOOD STREET CONSERVATION AREA ENHANCEMENT PROJECT**

Title: Phase 1 Plan - St Andrew's Road South (1 of 2)

Drawing Number: REG-002/17-SARS01



Stone upstand detail to planting beds to match existing on Wood Street and Park Road



Tegula block paving and sandstone paving detail



New lighting columns and lamps to be supplied by Urbis to match existing



Tree pit detail